



PD10R and PD100FR-CU Specification Sheet

Snow Guards

Part 1 – GENERAL

1.1 SUMMARY

A. WORK INCLUDES

1. PD10R and PD100FR-CU gusseted snow guard that hooks over shingle.
2. Coordinate with roof installation to assure proper placement of snow guards.

B. RELATED SECTIONS

1. Section 076000: Flashing and Sheet Metal	MasterFormat 2016 07 60 00
2. Section 073100: Shingles and Shakes	MasterFormat 2016 07 31 00
3. Section 073200: Roof Tiles	MasterFormat 2016 07 32 00
4. Section 077253: Snow Guards	MasterFormat 2016 07 72 53

1.2 SYSTEM DESCRIPTION

A. COMPONENTS

1. PD10R and PD100FR-CU snow guard system consists of individual metal snow guards.

1.3 SUBMITTAL

- A. Submit manufacturer's specifications, standard detail drawings, installation instructions, and recommended layout.

1.4 QUALITY ASSURANCE

- A. Installer to be experienced in installation of specified roofing material and snow guards for not less than 5 years in the area of the project.

1.5. DELIVERY / STORAGE / HANDLING

- A. Inspect material upon delivery and order replacements for any missing or defective items. Keep material dry, covered and off the ground until installed.



PD10R and PD100FR-CU Specification Sheet

Snow Guards

Part 2 – PRODUCTS

2.1 MANUFACTURER

A. Alpine SnowGuards®, a Division of Vermont Slate & Copper Services, Inc.
289 Harrel St., Morrisville, VT 05661 | 888-766-4273 | www.alpinesnowguards.com

2.2 MATERIALS

- A. Copper – Strap, cap and gusset are 16 oz copper. Fleur-de-lis embellishment is *only* available in copper and has a minimum material thickness of .040.
- B. Lead-Coated Copper – 16 oz lead-coated copper.
- C. Aluminum – .032 aluminum.
- D. Freedom Gray™ – 16 oz tin-zinc coated copper.
- E. Rheinzink® – .8mm Rheinzink®.

2.3 FINISH (choose one)

- A. Mill Finish – standard.
- B. Powder Coated – available at additional cost.
(Not available for PD100FR-CU)
- C. Kynar 500® pre-painted coil – aluminum only.
(Not available for PD100FR-CU)

Part 3 – EXECUTION

3.1 EXAMINATION

A. SUBSTRATE

1. Inspect structure on which snow guard system is to be installed and verify that it will withstand any additional loading it may incur. Notify general contractor of any deficiencies before installing Alpine SnowGuards' products.
2. Verify roofing material has been installed correctly prior to installing snow guards.

3.2 INSTALLATION

- A. Comply with architectural drawings and snow guard manufacturer's recommendations for location of system. Comply with manufacturer's written installation instructions for installation and layout.

Document Version 04.26.2023

07 72 53 Snow Guards